

Fukushima & Three Mile Island Events: Advancing Nuclear Safety

**HOUSE COMMITTEE ON SCIENCE, SPACE AND TECHNOLOGY:
SUBCOMMITTEES ON INVESTIGATIONS AND OVERSIGHT AND ENERGY
AND ENVIRONMENT
MAY 13, 2011**

**Lake H. Barrett
Rockville, MD**

Disclaimer: Fukushima Information is preliminary especially regarding interpretation of events; opinions expressed are mine and mine alone.

Fukushima Daiichi Nuclear Power Station



**Common
Spent Fuel
Pool**

Units 5 & 6

Dry SNF Storage

Units 1-4

Event Initiation


March 11, 2011

- About 14:46, a 9.0 magnitude earthquake struck (Plant design basis earthquake: 8.2)- **Plant safety systems reportedly function satisfactorily.**
- Units 1, 2 & 3 Scram & Unit 4 has 100 day old core offloaded into Unit 4 Spent Fuel Pool
- ~ 15:45, a tsunami 14 meters high inundated the site, whose design basis was 5.7 meters – the reactors and backup diesel power sit roughly 10 to 13 meters above sea level
- The impacts up and down the northeast coast resulted in tragic loss of 20,000+ lives, damage, and destruction of infrastructure.



By Janet Loehrke, USA TODAY

Subduction Fault




Tsunami Waves




Tsunami Size: Main Safety Factor

3/11 15:45



Battery Power Control of Steam-Driven Reactor Core Isolation Cooling System In Units 2 &3 (Unit 1 Had Isolation Condenser which Boiled Dry)




3/11 15:45 JST



CST?

3/11 15:45 to ~ 3/11
24:00 JST

Battery Power Exhausted




Core Uncovers and starts to overheat

Suppression pool (wet well) becomes saturated

3/12 ~02:00 JST

Venting Primary Containment



**Core Overheated
Fuel Cladding Oxidizes
Hydrogen Generated**

**Primary Containment Pressure
~ 90psia @02:00 3/12**

3/12 ~05:30 U1

3/13 ~ 00:00 U2

3/13 ~ 08:40 U3

Unit 1 Reactor Building Explosion

3/12 15:31



Unit 3 Reactor Building Explosion

3/14 11:15




Bleed & Feed Core Cooling Established

Seawater Injection Started Using Fire Engine Pump

Shift to Fresh Water Injection: To Dissolve Possible Salt Cakes

Vapor Venting



Water Spray to Unit 3 Pool Area



Unit 4 Reactor Building

Water Injection Boom To Spent Fuel Pool




Three Mile Island Units 1 & 2

March 28, 1979



Three Mile Island March 28, 1979




Hydrogen
Deflagration
28psig 13:00




~3M deep
water
~1000R/hr

Precautionary 5 Mile
Evacuation Issued

TMI Core Damage Sequence



High Rad Reactor Water Cleanup System Installed in Spent Fuel Pool



TMI Damaged Core Removal

~1985-1990



Three Mile Island History

- Reactor Scram: 04:00 3/28/79
- Core melt and relocation: ~ 05:00 – 07:30 3/28/79
- Hydrogen Deflagration: 13:00 3/28/79
- Recirculation Cooling: Late 3/28/79
- Phased Water Processing: 1979-1993:Removed ~1.2MCi Cs137
- Containment Venting 43KCi Kr-85: July 1980
- Containment Entry: July 1980
- Reactor Head removed and core melt found: July 1984
- Start Defuel: October 1985
- Shipping Spent Fuel: 1988-1990
- Finish Defuel: Jan 1990
- Evaporate ~2.8M gallons Processed Water: 1991-93
- Cost: ~\$1 Billion

Fukushima Stabilizing

- **Working to Establish Recirculation Core Cooling**
- **Mitigate Airborne Releases**
- **Mitigate Water Releases**
- **Gain Building Access to Start Recovery Activities**
- **Maintain Personnel Safety: High Rad Areas**
- **Reduce and Mitigate Evacuation Zone Impacts**

Units 1-4 After U4 Spent Fuel Pool Explosion

3/16



Unit 3 & Unit 4



Soil/Dust Suppression Resin Application



Contaminated Water Containment Overflow from U2 Reactor Bldg to Turbine Bldg to Intake Structure Wall Crack to Sea

~130KCi Released this Path

~Total Site Cs137(to 4/12) Released 300KCi

-Reference Chernobyl was 2M Ci Cs-137 released



**Non-Safety Grade
intake Structure**



**Radioactive Water
Leak 11-04-02**



**Leak Reduced 11-04-04
Leak Sealed 11-04-06
Sodium Silicate Injection**

Decontamination-Cleanup

High Radiation Field Work with Remotely Operated Equipment




**Remote Equipment
Operator**



**Remotely Operated
Construction Equipment
Reducing Gamma Field and
Debris Removal**


Offsite Impacts

Future Institutional Challenges But Minimal Health Impact



UNCLASSIFIED

Nuclear Incident Team DOE NIT
Contact (202) 586 - 8100



Dose Impact Projections

Cesium Ground Deposition
~ Ten+ KCi Cs Deposition

Personal Fukushima Observations

- **Not a Public Health Catastrophe**
 - Nuclear Impacts Inconsequential Compared to Earthquake/Tsunami Impacts
- **Is An Industrial Plant Catastrophe**
 - The tsunami was the Main Safety Issue
 - Three Severely Damaged Cores and Some Damaged Spent Fuel Pool inventories
 - Units 1-4 Complete Loss, Units 5 &6 Technically Recoverable
 - Cleanup Long & Expensive, but Technically Achievable (Much Larger than TMI)
- **Energy Dissipation is Getting Better, but Challenging**
 - Aftershock Safety
- **Environmental Release Mitigation is a Growing Challenge**
 - Continued Feed & Bleed Vapor/Water Radioactive Effluents
 - Environmental Mitigation, Social, Political & Economic Issues
 - Institutionally Challenging Infrastructure Issues Ahead

Personal U.S. Nuclear Safety Observations

- **Current Reactors Have Adequate Safety Margins**
 - U.S. Tsunami Risks are Limited To Only A Few U.S. Sites
- **Past Risk Informed Severe Accident Improvements Have Already Addressed Many Fukushima Issues**
 - Station Blackout & 911 Improvements
- **Systematic, Methodical, & Risk Informed Fukushima Lessons Learned Evaluations Are Appropriate**
 - Industry
 - NRC
 - Resist “Quick Fix” Emotional Reactions
 - Continuous Improvement Culture Will Further Strengthen U.S. Capabilities
- **Lessons Learned From TMI Lessons Learned**
 - TMI Lessons Learned Greatly Improved US Nuclear Safety and Productivity
 - Most Painful Lessons are the Most Teachable
 - Fukushima Lessons Should Improve Safety and Advance Global & U.S. Nuclear Energy As Three Mile Island Lessons Learned Did Thirty Years Ago.